

# **Three Mile Island Unit 2 Key Decisions and Important Events for Removing the Damaged Fuel**



Presented at the  
1st International Forum on the Decommissioning of the  
Fukushima Daiichi Nuclear Power Station

April, 2016



Chuck Negin  
Washington Grove, Maryland, USA  
charlesnegin@gmail.com

# Damaged Fuel and Debris

## TMI-2 Core End-State Configuration



# Damage Examples




TMI-2 Overview

# Various Areas for Defueling

- ❑ Core Cavity
- ❑ Lower Support Grid
- ❑ Flow Distributor
- ❑ Behind and within the Core Baffle Plates
- ❑ Lower Head
- ❑ Elsewhere in the Reactor Systems




Bottom of the Upper Core Support Assembly



Reactor Pressure Vessel Cutaway View

# Defueling Progress and Key Impacts



# Removal Methods


- ❑ Five concepts for fuel removal before visual characterization; none were used:
  - Dual Telescoping Tube, Manipulator
  - Manual Defueling Cylinder
  - Indirect Defueling Cylinder
  - Flexible Membrane
  - Dry
- ❑ Later, a remotely operated service arm, shredder, and vacuum transfer system was considered and rejected
- ❑ Final method chosen was an adapted mining drill (the core bore) and manual methods

# Core Boring Machine

- ❑ Adapted from commercial mining drilling equipment
- ❑ One of the most important machines for the project
- ❑ First use with hollow core bits: 10 samples 1.8 m long x 6.4 cm diameter (figure below)
- ❑ Second use with solid face bits to chew through the hard once-molten mass in the core region
- ❑ Third use was assisting lower grid and instrument tubes by grinding metal (next viewgraph)




**Tungsten Carbide Teeth with Synthetic Diamond**



# Fuel Removal Tools and Equipment

## □ Some Manual Tools



## □ Powered Equipment


- Core Boring Machine
- Plasma Arc
- Power Assisted shears
- Bulk Removal
- Water Vacuum and Air Lift

## □ Manual Controlled Equipment


- Grippers
- Buckets




# Work Platform




# Three Canister Design – 341 Shipped



**271 Fuel & Debris Canisters**



**10 Knockout Canisters  
(for vacuum tools)**



**60 Filter Canisters  
(water processing)**

# Packaging & Transport




**Canister Staging in Spent Fuel Pool**




**Transfer Cask Operations**

# Staging & Shipping



**Loading the Shipping Cask**



**Shipping Cask**

# Packaging, Transport, & Storage at Idaho




**1986 to 1990**

**341 canisters of fuel & debris in  
46 shipments by rail cask to the  
Idaho National Laboratory**



**1990 to 2000**

**Wet Storage in Spent Fuel  
Storage Pool**




**2000 – 2001**

**Removed from pool, dewatered,  
dried, and placed in dry storage**

# Possible Remaining Fuel Particulate

- ❑ Residual Fuel\*
  - RPV: < 900 kg
  - In the Reactor Coolant System: < 133 kg
  - Criticality ruled out by analysis
- ❑ Assessment Required a Combination of\*
  - Video inspection for locations
  - Gamma dose rate and spectroscopy
  - Passive neutron solid state track recorders, activation, BF3 detectors
  - Active neutron interrogation
  - Alpha Detectors
  - Sample Analysis



# Events/Decisions(1)

Events/Decisions	Significance
Decisions for removal required visual characterization	First idea of what conditions really were; complete assessment took another year; could not proceed to plan defueling without this knowledge
Decision to not to install in-core shredding equipment in the vessel	<ul style="list-style-type: none"> <li>• New application for the proposed technology, concern that failure would cause problems, relied mostly on manual manipulation with power assist</li> <li>• Allowed defueling to start earlier, knowing that overall schedule would not be minimized. This was preferred over a 3 year development for a remote system/equipment</li> </ul>
Decision to leave refueling canal dry	<ul style="list-style-type: none"> <li>• Less depth for manually operated tools</li> <li>• Shielded work platform 2m above the reactor pressure vessel flange</li> <li>• Reduced need for water processing</li> <li>• Dose rates were low within the refueling canal</li> </ul>
Use of Core Boring Machine was essential	<ul style="list-style-type: none"> <li>• Samples of the fuel and debris that was melted together</li> <li>• Breaking up the crust and molten mass when manual methods were unsuccessful</li> </ul>

# Events/Decisions(2)

Events/Decisions	Significance
Unanticipated biological growth in water fouled filters	Caused a year delay; managing water clarity is extremely important
DOE to take Fuel & Debris New cask design and license Ship Fuel to Idaho by Rail and not Truck	<ul style="list-style-type: none"><li>• Handling and shipping design and fabrication could not take place until destination was determined</li><li>• Allowed fuel &amp; debris canisters to be removed from TM</li><li>• New cask could be designed for the TMI canisters</li><li>• Fewer shipments</li></ul>
Transfer to Dry Storage	Long term storage stability, also allowed demolition of fuel pool at Idaho