

# Approaches to the decommissioning and contaminated water management for Fukushima Daiichi Nuclear Power Station


1st International Forum on Decommissioning of  
Fukushima Daiichi Nuclear Power Plant

April 10th, 2016

Hajimu Yamana  
President, Nuclear Damage Compensation and  
Decommissioning Facilitation Corporation

# Review of the Fukushima Daiichi Nuclear Power Station Accident

Regulated area  
as of Sep. 5, 2015



Restricted area	Evacuees As of Oct.2015
Difficult-to-return	24, 000
Restricted residence	23, 000
Evacuation cancellation preparation	24, 000



## Released radioactivity

Nuclide	Half-life	Chernobyl [1] PBq	Fukushima-Daiichi [2][3] PBq
Xe-133	5.25h	6, 500	14, 000
I-131	8.03d	1, 760	150
I-133	20.8h	910	146
Cs-134	2.07y	47	11.8
Cs-137	30.1y	85	12

[1] UNSCEAR (2008), [2] Chino et al. (2011, 2013),  
[3] Steinhauser et al. (2014)

# Changes in five years since the accident

**2011**

**2012**

**2013**

**2014**

**2015**

**Government**

Nuclear Emergency Response  
Headquarters 2011.03.11

Local nuclear emergency response  
headquarters 2011.03.11

Council for the Decommissioning of  
TEPCO's Fukushima Daiichi NPS  
2013.09.03

Committee on Countermeasures  
for Contaminated Water Treatment  
2013.04.19

Team for Countermeasures for  
Decommissioning and  
Contaminated Water Treatment  
2013.09.10

**Roadmap**

**Roadmap  
1st issue**  
2011.12.26

**Roadmap  
1st revision**  
2012.12.26

**Roadmap  
2nd revision**  
2013.06.27

**Roadmap  
3rd revision**  
2015.06.12



**2011.03.11**

**Cold  
shutdown**  
2011.12.16

**Strategic Plan**

**Strategic  
Plan2015**  
2015.04.30

**Emerging entities**


**NDF**  
2014.08.18

**IRID**  
2013.08.01


**TEPCO D&D Co.**  
2014.04.01

# Update of Units 1-4


## Unit 1




## Unit 2



## Unit 3



## Unit 4



Removal of last one roof panel



Policy decision for the overall disassembly of storage shed



During preparation of retrieval/decontamination




Completion of spent fuel

# Retrieval of fuel debris from Unit3

- ◆ The removal of the spent fuels stored in the pools of Unit-1, 2, and 3 is urgently required operation.
- ◆ They are planned to be taken out after clearing off the radioactive rubbles existing on the operation floor.
- ◆ The decontamination and clearing off of the operation floor of Unit-3 has progressed, and the removal of rubbles fallen down into the pool has started.
- ◆ After the decontamination, a building cover will be installed to remove the fuels with newly installed Fuel Handling Machine.




Removal of rubles from SF pool of U-3



Building cover to be installed




Building covers under fabrication




Rubble removal operation



# Improvement of site condition




# Approaches to the contaminated water purification



- ◆ Contaminated water is generated by the inflow of ground water into the reactor buildings. The total amount of the accumulated water exceeds 800 k m<sup>3</sup> to date.
- ◆ It has been treated by using ALPS, Advanced Liquid Processing System, and Mobile Sr-Removal system to remove major radio-nuclides, and residual tritiated water is stored in tanks.



# Approaches to the contaminated water



**Contaminated Water Treatment**

Water treatment facility special for Subdrain & Groundwater drain  
Temporary storage tanks

**Groundwater Bypass**

2014/5  
Discharge started

**Subdrain**

2015/9  
Pumping-up started

**Land-side Impermeable Wall (Frozen Soil wall)**

2015/3  
Operation started

**Seawater Piping Trench**

**Groundwater Drain**

**Sea-side Impermeable Wall**

2015/7  
Water removal completed


2016/2  
Closing completed



Cooling pipe installation



Sub-drainage treatment



Frozen wall




Refrigeration facility


Source : TEPCO website and photo archive



# Accumulated contaminated water




# Organizational structure for decommissioning of Fukushima Daiichi



# Mid-and-long-term Roadmap and Technical Strategic Plan

## Mid- and Long-term Roadmap by GOJ




## Strategic Plan by NDF

**Strategic Plan 2015 :**  
**Issued on Apr. 30, 2015**

**Strategic Plan 2016:**  
**Scheduled for this summer**

- ◆ Discussion through the close dialogue and exchange of information between the Government and TEPCO.
- ◆ Study mid-term technical strategy through the discussion with the experts from various technical fields while receiving the advise from Decommissioning Strategy Board, Expert Committee from multiple fields, International Special Advisors.
- ◆ "Risk reduction strategy" regarding mid- and long-term decommissioning
- ◆ In vessel inspection and study of the technical strategy for the fuel debris retrieval method.
- ◆ Develop an optimum technical strategy based on the Five Guiding Principles. " Safe, Proven, Efficient, Timely and Field-oriented"

# Fuel debris retrieval




- Operation floor largely damaged. High dose rate
- Spent fuels stored in Unit1, 2 and 3
- Fuel debris dispersed in both RPV and PCV  
Properties unknown
- High radiation inside PCV  
Inside PCV gradually known.
- Cooldown by water injection required.
- Building highly contaminated with high radiation (battle with decontamination)
- Leakage from PCV.  
Generation of contaminated water.
- Leakage from the building.  
Penetration of groundwater.  
Needs of contaminated water leakage prevention

# Internal inspection for reactor containment vessel


- ◆ Internal inspection for reactor containment vessel using robots and other remote techniques are the keys to determine the fuel debris removal method.

## Muon-tomography adopted to Unit-1

Measurement for 3 months



Simulation



## Shape-changing crawler robot

PCV inside (unit-1)




## Traveling through piping




Transformation

## Traveling on grating




# Fuel debris retrieval method




**Submersion -  
Top entry method**

Assuming the in-core  
structures above the fuel  
debris are removed



**Partial submersion -  
Top entry method**

Assuming that the in-core  
structures above the fuel  
debris are removed




**Partial submersion -  
Side entry method**

Assuming that the equipment and  
other objects outside RPV pedestal in  
PCV are removed

# Decommissioning as risk reduction


## Risk defined in the Technical Strategic Plan 2015 by NDF, Japan

Fig. 3-5 shows the levels of risks for major risk sources in the Fukushima Daiichi NPS based on the "hazard potential" and "likelihood of loss of containment function"



# Integration from basic research to practical application

- It is important to facilitate interaction among researchers and engineers involved in R&D initiatives.
- The Decommissioning R&D Partnership Council integrates management from fundamental research to practical application.





# Approaches to the decommissioning

- ◆ While accelerating the stabilization of the contaminated water management, risks which may be exposed in a short period of time should be eliminated as quickly as possible, such as removal of spent fuels.
- ◆ Realize the stable state where the risks would not be exposed by promoting the fuel debris retrieval and other "cleanup after the accident" and removing a short- and mid-term risk derived from the reactor building.  
Study final decommissioning while continuing the inspection and monitor of the inside of the reactor.
- ◆ Securing the "Low risk state" that does not have impact on the residents and environment and developing reasonable decommissioning strategy so that the people in Fukushima can make their all effort to the restoration of hometown.

Reference: Concept of decommissioning defined by IAEA



# Thank you for your Attention!

